CONSULTANT ENGINEERING SERVICE, INC.
PLUMBING ▪ MECHANICAL ▪ ELECTRICAL
A Woman Owned Business
est. 1964
Phone: 336.724.0139 ▪ 1111 S Marshall Street, Suite 250, Winston Salem, NC 27101

Southwest Guilford Elementary School
HVAC Renovation, Job #4022
Addendum #4, May 15, 2020

Fencing Clarification

Chain link fences shall commercial grade, be 8 feet high 9 gauge, 2" mesh, galvanized steel fabricated in one piece widths. End, gate, and pull posts shall be 2-3/8" od galvanized steel pipe. Line posts shall be 2-3/8" od galvanized steel pipe. Line posts shall be spaced at not more than 10'-0" o.c. Top and bottom rails pipe sections shall be not less than 18' long and shall be fitted with couplings for connected lengths into a continuous run. Couplings shall be not less than 6' long with a .070" wall thickness and shall allow for expansion and contraction of the top rail. The top rail shall pass thru the line posts. The rail shall be securely connected to end and corner posts with galvanized steel connectors. Gates shall have a frame fabricated from 1-7/8" od galvanized steel pipe. With either welded joints or securely connected with galvanized steel connectors. The complete installation shall be in accordance with the fence systems manufactures written instructions. Fence posts shall be set in place prior to concrete pads being poured.

Pipe Trench:

A concrete base is not required

END OF ADDENDUM #4