

Hugh Creed Associates, Inc. P.A.

Consulting Engineers & Land Surveyors

1306 W. WENDOVER AVENUE

GREENSBORO, N.C. 27408

TELE: (336) 275-9826 OR (336) 275-8084

FIRM LICENSE #C-0551

P.O. BOX 9623

GREENSBORO, N.C. 27429

FAX: (336) 275-3379

E-MAIL: HCA@HUGHCREEDASSOCIATES.COM

ADDENDUM #1

April 22, 2019

Southern Guilford Elementary School Driveway Paving Improvements

To All Bidders:

Contractors submitting proposals for the above-named project shall take note of the following changes, additions, deletions, and clarifications on the Bid Documents, which shall become a part of and have precedence over anything contrarily shown or described in the Bid Documents.

1. No pipe extensions will be needed at the drive entrance radii at Drake Road.
2. The pipe extension at the turn away from the existing bus parking lot towards the elementary school will require tail ditching the existing ditch to ensure proper drainage at the end of the new pipe. The new ditch will be lined with excelsior matting and seeded.
3. Any signs removed for construction must be replaced near the location it was removed from as directed by the Owner's representative.
4. At the extended radii at Drake Road:
 - a. No fencing will be removed on the north side radius.
 - b. The radius on the south side will be adjusted as necessary to avoid the power pole guy wires and to grade a small ditch between the guy wires and the new paving radius.
5. The binder layer can be changed to 119.0C hot mix binder instead of 119.0B.